


BUILDING PERFORMANCE ASSESSMENT TEAM

Hurricane Fran in North Carolina

**OBSERVATIONS,
RECOMMENDATIONS, AND
TECHNICAL GUIDANCE**



FEDERAL EMERGENCY MANAGEMENT AGENCY
MITIGATION DIRECTORATE





FEDERAL EMERGENCY MANAGEMENT AGENCY

FEMA Building Performance Assessment Teams

■ **Team Objectives**

- **Inspect damage to buildings**
- **Assessment performance of buildings**
- **Evaluate design and construction practices**
- **Evaluate code requirements and enforcement**
- **Make recommendations as necessary**

BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY


FEMA Building Performance Assessment Teams

- **Team Members**
 - **Representatives of public and private sectors and expertise in:**
 - structural and civil engineering
 - building design and construction
 - code development and enforcement

BUILDING PERFORMANCE ASSESSMENT TEAM




FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY

Observations

- **Building Types**
 - **Wood-frame on pilings**
 - **Wood-frame on slab-on-grade foundations**
 - **Wood-frame on continuous masonry wall foundations**
 - **Manufactured homes on dry-stacked masonry block foundations**



FEDERAL EMERGENCY MANAGEMENT AGENCY

Observations

- **Damaged Observed**
 - **Leaning and collapsed buildings**
 - **Undermined continuous foundation walls**
 - **Collapsed decks, porches, and roof overhangs**
 - **Broken vertical foundation members**
 - **Broken cross-bracing on piling foundations**

BUILDING PERFORMANCE ASSESSMENT TEAM



Observations

- **Damaged Observed** *(continued)*
 - **Undermined below-building concrete slabs**
 - **Exposed septic tanks**
 - **Loss of electrical, water, and sewer lines**
 - **Collapsed AC/heat pump compressor platforms**



Observations

- **Damaged Resulted From:**
 - Erosion of frontal dunes and beach profile
 - Localized scour around pilings and continuous foundations
 - Velocity flow, wave action, and debris impact on:
 - vertical foundation members
 - cross-bracing of piling foundations
 - walls of below-building enclosures



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY

Observations

■ Erosion

- Affected oceanfront buildings
- Lowered beach profile 2 to 3 feet
- Lowered grade 4 to 6 feet below buildings
- Exacerbated by previous effects of Bertha



FEDERAL EMERGENCY MANAGEMENT AGENCY



PRE-STORM
GRADE

BUILDING PERFORMANCE ASSESSMENT TEAM




FEDERAL EMERGENCY MANAGEMENT AGENCY

Observations

- **Localized Scour**
 - **Affected oceanfront and landward buildings**
 - **Depth of scour = 1 to 1.5 times diameter or width of vertical member**



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY

Observations

- **Erosion Plus Localized Scour**
 - **Completely exposed, or reduced embedment depth of foundations**
 - **Resulted in collapse of over 100 oceanfront buildings**
 - **Resulted in many other buildings leaning**



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY

Observations

- **Applicable Codes and Requirements**
 - **North Carolina Coastal Area Management Act (CAMA) - building setback for erosion protection**
 - **North Carolina State Building Code - piling embedment depth**
 - **NFIP requirements**




Observations

- **Minimum CAMA Setback Requirements (from first line of stable natural vegetation)**
 - **Single-family homes and commercial/multi-family buildings <5,000 square feet**
 - 30 x erosion rate (minimum of 60 feet)
 - **Commercial/multi-family buildings >5,000 square feet**
 - 60 x long-term erosion rate (minimum 120 feet)



FEDERAL EMERGENCY MANAGEMENT AGENCY





Observations

- **State Building Code Embedment Requirements for Main Structure Pilings**
 - **Pre-1986 - 8 feet below grade for all structures**
 - **Post-1985 - 16 feet below grade or -5 feet m.s.l., whichever is shallower, for structures in erosion-prone areas**




FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY

Observations

- **Effect of Federal and State Requirements**
 - **Buildings that met CAMA, 1986 State Building Code, and NFIP requirements outperformed all others**
 - **Post-Fran piling embedment depth study conducted on Topsail Island by FEMA contractor indicated value of deeper embedment requirement of 1986 State Code**

BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY

Observations

- **BPAT concerns about construction practices involve:**
 - **Piling and post embedment depths**
 - **Use of cross-bracing**
 - **Grade of lumber for pilings and cross-bracing**
 - **Use of continuous foundation walls**



Observations

- **BPAT concerns about construction practices involve:** *(continued)*
 - **Installation of breakaway walls for below-building enclosures**
 - **Construction of below-building concrete slabs**
 - **Installation of utility system components**




Observations

- **Piling and Post Embedment Depths**
 - **Shallow embedment depths on pre-1986 buildings**
 - **Shallow embedment depths on decks, porches, and roof overhangs on pre-1986 and post-1985 buildings**
 - **Shallow post embedment depths for AC/heat pump compressor platforms**



FEDERAL EMERGENCY MANAGEMENT AGENCY





FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



Observations

- **Use of Cross-Bracing**
 - Installed perpendicular to velocity flow and wave action
- **Grade of Lumber for Pilings and Cross-Bracing**
 - Use of lumber with excessive numbers of knots, cracks, or other defects for vertical foundation members and cross-bracing



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY

Observations

- **Continuous Foundation Walls**
 - **Use in A-zone areas susceptible to high velocity flow**



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



Observations

- **Breakaway Walls**
 - Placement seaward of cross-bracing
 - Installation of sheathing continuously across vertical foundation members
 - Attachment methods that prevented breakaway (e.g., too many fasteners)



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY

Observations

- **Below-Building Concrete Slabs**
 - Slabs too thick (i.e., >4 inches)
 - Inadequate number of contraction joints
 - Use of wire mesh in slabs
 - Slabs connected to vertical foundation members



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY

Observations

- **Below Building Concrete Slabs**
(continued)
 - **Slabs and grade beams cast monolithically**
 - **Use of concrete collars around vertical foundation members to support slabs**



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM




FEDERAL EMERGENCY MANAGEMENT AGENCY

Observations

- **On-Site Utility Systems**
 - **AC/heat pump compressor platform support posts not embedded deep enough**
 - **Unanchored AC/heat pump compressors**
 - **System components on or adjacent to breakaway walls**



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM




FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM




FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM




Observations

- **On-Site Utility Systems** *(continued)*
 - System components installed on seaward faces of vertical foundation members nearest ocean
 - Septic tanks installed on ocean side of building




FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM




FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM




Recommendations

- **Piling and Post Embedment Depths**
 - In absence of State/local requirements, embedment depth for pilings in erosion-prone areas should be -10 feet m.s.l.
 - State of North Carolina should consider requiring embedment of 16 feet below grade or 5 feet m.s.l., whichever is deeper
 - Embedment depths for deck, porch, and roof overhang pilings should be same as for main building



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY

Recommendations

- **Other Foundation Issues**
 - **Design foundations to resist flood/wind forces without cross-bracing**
 - **Require engineering analysis of potential scour before permitting solid foundation walls in landward areas subject to high-velocity flow**



FEDERAL EMERGENCY MANAGEMENT AGENCY

Recommendations

- **State and Local Requirements**
 - Consider adding code requirements regarding grade of lumber used for pilings and cross-bracing
 - Consider requiring that buildings be elevated above the BFE



FEDERAL EMERGENCY MANAGEMENT AGENCY

Recommendations

- **Manufactured Homes**
 - **Protect foundation from scour (e.g., geotextile fabric, non-scourable soil, extend below scour depth)**
 - **Periodically check anchor straps for corrosion and proper tension**



Recommendations

- **Manufactured Home** *(continued)*
 - Use proper size and type of anchor for soil conditions on site
 - In all coastal flood areas, elevate home so that bottom of chassis I-beam is above BFE




FEDERAL EMERGENCY MANAGEMENT AGENCY

Recommendations

- **Breakaway Walls**
 - Do not extend sheathing across vertical foundation members
 - Attach walls so that they will break away under flood forces
 - Do not install walls immediately seaward of cross-bracing




FEDERAL EMERGENCY MANAGEMENT AGENCY



TOP VIEW



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM




FEDERAL EMERGENCY MANAGEMENT AGENCY

Recommendations


- **Below-Building Slabs**
 - Limit slab thickness to 4 inches
 - Install adequate number of contraction joints
 - Do not use wire mesh



FEDERAL EMERGENCY MANAGEMENT AGENCY



DETAIL - SECTION THROUGH SLAB



NOTE: INSTALL EXPANSION AND ISOLATION JOINTS AS APPROPRIATE IN ACCORDANCE WITH STANDARD PRACTICE OR AS REQUIRED BY STATE AND LOCAL CODES.



FEDERAL EMERGENCY MANAGEMENT AGENCY

Recommendations

- **Below-Building Slabs** *(continued)*
 - Do not connect slabs to vertical foundation members
 - Do not cast slabs/grade beams monolithically
 - Do not install concrete collars around vertical members under slabs




Recommendations

- **On-Site Utility Systems**
 - **Embed vertical members for AC/heat pump compressor platform to same depth as those for main building, or use cantilever platform**
 - **Anchor compressor to resist wind**



FEDERAL EMERGENCY MANAGEMENT AGENCY




Mechanical platform supported by pilings.

BUILDING PERFORMANCE ASSESSMENT TEAM



FEDERAL EMERGENCY MANAGEMENT AGENCY



BUILDING PERFORMANCE ASSESSMENT TEAM



Recommendations

- **On-Site Utility Systems** *(continued)*
 - Do not place utility system components on, through, or adjacent to breakaway wall panels
 - Locate utility system components on landward faces of vertical foundation members farthest from ocean
 - Locate septic tanks as far landward as possible



FEDERAL EMERGENCY MANAGEMENT AGENCY

